

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20322-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 12-16S-43W
1200 feet from N Section Line, 650 feet from E Section Line
Lease/Unit Name: OTIS Well Number: 4
County: GREELEY Total Vertical Depth: 5275 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

Conductor Pipe: Size _____ feet: _____
Surface Casing: Size 8.625 feet: 464 WITH 250 SX CMT *S 171.44*
Production: Size 4.5 feet: 5275 WITH 220 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/04/2001 12:30 PM
Plug Co. License No.: 32524 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC
Proposal Rcvd. from: M.L. COX Company: HERMNA L. LOEB Phone: (316) 564-3343

Proposed Plugging Method: RUN TUBING IN HOLE TO 3400'. PUMP 40 SX CMT WITH HULLS MIXED IN. PULL TUBING OUT OF HOLE. SET CIBP AT 1650'. PERFORATE AT 1600'. PUMP 80 SX CMT OVER CASING CAPACITY. PUMP 200 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/04/2001 5:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 5146-72'. TUBING FISH AT 3460'. CASING LEAK BELOW 2000'. RUN TUBING IN HOLE WITH 4 1/2" PACKER TO 2000' TESTED CASING TO 300#. RUN TUBING IN HOLE TO 3400'. PUMP 200# HULLS & 40 SX CMT. PULLED TUBING OUT OF HOLE. SET CIBP @ 1650'. PRESSURE TESTED 4 1/2" CASING TO 800#. PERFORATE AT 1600'. PUMP DOWN 4 1/2" 2.5 BBL PER MINUTE AT 600#. STARTED CMT PUMPED 170 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN AT 500#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 200 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN AT 100#.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Kevin D Strube
(TECHNICIAN)

RECEIVED
12-7-01
DEC 07 2001
KCC WICHITA

INVOICED
DATE 12-10-01
NOV. NO. 2002061048
DEC 06 2001
AP

[Signature]
KCC CR-23