

1080263

TO: STATE CORPORATION COMMISSION

9-8

API NUMBER 15-071-20,316-0000
NE SW NW SEC. 12, T 16 S, R 43 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ROSENBERG A WELL # 4

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY

OPERATOR LICENSE # 3273

WELL TOTAL DEPTH 5300 FEET

172.25

OPERATOR: HERMAN L. LOEB PRODUCTION CSG: SIZE 4 1/2" @ 5292' WITH 170 SX

NAME AND PO BOX 524 SURFACE CASING: SIZE 8 5/8" @ 454' WITH 250 SX

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING COMPANY INC LICENSE NUMBER NA

ADDRESS PO BOX 31 RUSSELL, KS 67665-0031

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 08 MONTH: 09 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM SHANE PELTON

(COMPANY NAME) ALLIED CEMENTING (PHONE) 785-483-2627

WERE: PERFS AT 1010-22. CIBP @ 5100' W/ 2 SX CEMENT. DV @ 1767' W/ 250 SX CEMENT

2ND STAGE CEMENT BOND FROM 330' TO 1800'.

PUMP DOWN 4 1/2 CASING 140 SX CEMENT WITH 200# HULLS AHEAD. MAXIMUM PSI @ 1000#. SHUT IN WITH

600#. PUMPED DOWN 8 5/8 X 4 1/2 ANNULUS 70 SX CEMENT. MAXIMUM PRESSURE AT 100#. SHUT IN WITH

100#.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 10:45 AM DAY: 08 MONTH: 09 YEAR: 1999

ACTUAL PLUGGING REPORT

ALLIED CEMENTING PUMPED DOWN 4 1/2" CASING 140 SX CLASS A CEMENT WITH 200# HULLS AHEAD.

MAXIMUM PSI @ 1000#. SHUT IN WITH 600#. PUMPED DOWN 8 5/8 X 4 1/2 ANNULUS 70 SX CLASS A

CEMENT. MAXIMUM PRESSURE AT 100#. SHUT IN WITH 100#.

RECEIVED
STATE CORPORATION COMMISSION

INVOICED

OCT - 6 1999

10-6-99
CONSERVATION DIVISION

Wichita, Kansas

DATE 10-11-99

REMARKS: USED CLASS A CEMENT BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin D. Strube
(TECHNICIAN)

FORM CP-2/3

(Handwritten signature/initials)