

1 060475

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,328-0000

NE SE NW, SEC. 12, T 16 S, R 43 W XX

3630 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Rosenberg Well # A-5

Operator: TXO Production Corp.

County Greeley 172.25

Name & Address 200 W. Douglas, Suite 300

Well Total Depth 5300 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 493

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor J. W. Gibson Well Service Co. License Number 5866

Address 3025 Parker Road, # 711, Aurora, CO 80010

Company to plug at: Hour: 4:00 pm Day: 17 Month: January Year: 19 85

Plugging proposal received from Frank Tsuru

(company name) TXO (phone) 303-861-4246

were: 4 1/2" set at 5299' PBTD 5264' Perfs at 5158-60'

1st plug CIBP set at 5100' with 2 sx cement

RECEIVED

Spot plugs through 4 1/2" casing with mud between plugs

STATE CORPORATION COMMISSION

2nd plug at 1154' with 25 sx cement

FEB 04 1985

3rd plug at 500' with 25 sx cement

2-4-85

solid bridge

CONSERVATION DIVISION

4th plug hulls - plug at 40' Plugging Proposal Received by Paul A. Suthis

Wichita, Kansas

cement to surface with 10 sx cement

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:00 pm Day: 17 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug CIBP at 5100' with 2 sx cement, spotted plugs through

4 1/2" casing with mud between plugs, 2nd plug at 1154' with 25 sx cement, 3rd plug at

500' with 25 sx cement, 4th & 5th plugs - solid bridge- hulls - plug at 40' -- cement

to surface with 10 sx cement.

Remarks: Recovered 1154' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

(XXXXX) did not observe this plugging.

DATE 2-6-85

Signed Paul A. Suthis (TECHNICIAN)

INV. NO. 6856