

1 090819

6-8

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130, S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 071-20,671-0000
130' W OF
S/2 SW NW, SEC. 35, T 17 S, R 43 W/E

2310 feet from ~~N~~ section line
530 feet from ~~W~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 32058

Lease Name Sell Well # 1

Operator: DRW Operating Company

County Greeley 174.85

Name & Address P.O. Box 4462

Well Total Depth 5380 feet

Englewood, CO 80155-4462

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 362

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 30606

Address 250 N. Water, Ste. 300; Wichita, KS 67202

Company to plug at: Hour: 6:30 a.m. Day: 8 Month: 6 Year: 19 97

Plugging proposal received from Jim Renner

(company name) Murfin Drilling Co. (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2675' with 50 sx cement, 2nd plug at 1700' with 80 sx cement,

3rd plug at 800' with 50 sx cement, 4th plug at 370' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10 a.m. Day: 8 Month: 6 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2675' with 50 sx cement,

2nd plug at 1700' with 80 sx cement,

3rd plug at 800' with 50 sx cement,

4th plug at 370' with 40 sx cement, 5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE JUN 12 1997

INV. NO. 48328

6-8

Signed _____ (TECHNICIAN)

RECEIVED
KANSAS CORP COM
1997 JUN 11 10:25
6-11-97

EFFECTIVE DATE: 5-18-97

State of Kansas

FORM MUST BE TYPED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL 071-20,671-6000

FORM MUST BE SIGNED

SGA? ... Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date May 20 1997
month day year

Spot 130' W OF East
S/2 - SW - NW Sec 35 Twp 17. S Rg 43 West

OPERATOR: License # 32058
Name: DRW Operating Company
Address: P.O. Box 4462
Englewood, CO 80155-4462
City/State/Zip: Douglas E. Wood
Contact Person: (303) 629-1523
Phone:

2310' feet from South North line of Section
530' feet from East West line of Section

IS SECTION REGULAR IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License # 30606
Name: Murfin Drilling

County: Greeley
Lease Name: Sell Well #: 1

Well Drilled For: Well Class: Type Equipment:
 Oil ... Enh Rec ... Infield Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal Wildcat ... Cable
... Seismic; ... # of Holes ... Other

Field Name: WILDCAT
Is this a Prorated/Spaced Field? ... yes no

If OWWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Target Formation(s): MORROW
Nearest lease or unit boundary: 530'

Ground Surface Elevation: 3928' feet MSL
Water well within one-quarter mile: ... yes no

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Public water supply well within one mile: ... yes no
Depth to bottom of fresh water: 180'

Depth to bottom of usable water: 1700'
Surface Pipe by Alternate: ... 1 2

Length of Surface Pipe Planned to be set: 370'
Length of Conductor pipe required: N/A

Projected Total Depth: 5325'
Formation at Total Depth: _____

Water Source for Drilling Operations: _____
... well other

Will Cores Be Taken?: _____
If yes, proposed zone: _____

Exp. 11/13/97 **AFFIDAVIT**

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 15 1997
200' Alt. ID Rec

Pusher Jim Plummer/Murfin
SPUD DATE 5-29-97 INIT. SP
LENGTH SURFACE PLANNED 320' of 8 1/2"
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 362 CONDUCTOR
ANHYDRITE T- B- ELEVATION
TD 5380 FORMATION MUSS
RAN PIPE @ SX DV TOOL ALT II DONE
Arbuckle Plug @ SX Ft. W/ SX
Hug./Council @ SX Ft. W/ SX
1 Anhydrite Base @ 2675 Ft. W/ 50 SX
2 1/2 Base Anyh. @ 1700 Ft. W/ 80 SX
3 1/2, 1/2 Plug @ 800 Ft. W/ 50 SX
4 Bottom Surface @ 370 Ft. W/ 40 SX
5 40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond)
TECHNICIAN SM DATE 6-7-97 Hauling X
TYPE OF CEMENT 60/40 670 1/4 Low Seal
STARTING TIME 6:30 (AM/PM) DATE 6-8-97
COMPLETION TIME 10:00 (AM/PM) DATE 6-8-97
CEMENT COMPANY allied