

To: 1080039  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-Docket #D-19,522 15-071-20165-0001  
C SW SW, SEC. 22, T 17 S, R 39 W/X

5-2

660 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License 8450 (expired)

Lease Name Mai Twin Well 2  
County Greeley 99.93

Operator: Gary C. Adams Oil & Gas  
Name & Address: P.O. Box 21470  
Tulsa, OK 74121

Well Total Depth 3075 feet  
Conductor Pipe: Size            feet  
Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well            Gas Well            Input Well            SWD Well X O&A             
Other well as hereinafter indicated           

Plugging Contractor Allied Cementing License Number             
Address:           

Company to plug at: Hour: 12:30 p.m. Day: 2 Month: 5 Year: 19 96

Plugging proposal received from Wade Alexander  
(company name) Gary C. Adams Oil & Gas (phone) 918-582-7713

Work: 5 1/2" at 3068' w/500 sx cement, PBTD 3068', Perfs at 2923-3004'  
1st plug pump 2 sx hulls and 315 sx cement down 5 1/2" casing,  
2nd plug pump 50 sx cement down backside.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part            None           

Operations Completed: Hour: 1 p.m. Day: 2 Month: 5 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped down 8 5/8" X 5 1/2" with 5 sx cement. Pressured to 300 psi.  
2nd plug pumped down 5 1/2" with 400 lbs. hulls, and 270 sx cement.

Maximum pressure 700 psi and shut in 100 psi.

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 14 1996

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

CONSERVATION DIVISION  
WICHITA, KS

(If additional description is necessary, use BACK of this form.)

INVOICED  
MAY 22 1996  
observe this plugging.

Signed Kevin D. Stuts  
(TECHNICIAN)

DATE             
INV. NO. 45614 JUL 17 1996  
5-2