

1 050238

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-071-20,315 - 0000

NW NE NW, SEC. 11, T 16 S, R 43

1700 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Cheek Well # A-3

Operator: TXO Production Corp.

County Greeley

Name: 1800 Lincoln Center Building

Well Total Depth 5300 172.25 feet

Address: Denver, CO 80264

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 463

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor J.W. Gibson Well Service License Number 5866

Address 1204 East Burlington, Ft. Morgan, CO

Company to plug at: Hour: 5:00 am Day: 2 Month: June Year: 19 84

Plugging proposal received from Frank Sewer

(company name) J. W. Gibson (phone) 913-232-0564

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2700' with 50 sx cement 5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

2nd plug at 1800' with 50 sx cement

3rd plug at 1200' with 50 sx cement 7th plug to circulate rat hole with 10 sx cement

4th plug at 500' with 40 sx cement 8th plug to circulate mouse hole with 5 sx cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:00 am Day: 2 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2700' with 50 sx cement, 2nd plug at 1800' with 50 sx cement, 3rd plug at 1200' with 50 sx cement, 4th plug at 500' with 40 sx cement, 5th & 16th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 7th plug to circulate rat hole with 10 sx cement, 8th plug to circulate mouse hole with 5 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUN 07 1984 6-7-84 CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Dowell (if additional description is necessary, use BACK of this form)

I (did not) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 6-15-84

INV. NO. 2044 6-2