

1 020148

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,319-0000

NW NE SW, SEC. 11, T 16 S, R 43 W43

2310 feet from NW/S section line

330 feet from W43 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Cheek "A" Well # 4

Operator: TXO Production Corp.

County Greeley

Name & Address 1800 Lincoln Center

Well Total Depth 5293 172.02 feet

Denver, CO 80264

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 408

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor J. W. Gibson License Number 5866

Address 1204 East Burlington, Ft. Morgan, CO 80701

Company to plug at: Hour: 1:00 pm Day: 7 Month: May Year: 19 84

Plugging proposal received from Frank Tsuru

(company name) TXO (phone) 303-861-4246

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2400' with 50 sx cement

2nd plug at 1500' with 60 sx cement

3rd plug at 460' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement
Plugging Proposal Received by Sean J. Wilbur
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:50 pm Day: 7 Month: May Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 2400' with 50 sx cement; 2nd plug at 1500' with 60

sx cement, 3rd plug at 460' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

15 sx cement, 7th plug to circulate mousehole with 10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Dowell

(if additional description is necessary, use BACK of this form)

(date) did (not) observe this plugging.

INVOICED

DATE 5-15-84

INV. NO. 1512 MAY 23 1984

5-7

Signed Sean J. Wilbur
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1984
5-11-84
CONSERVATION DIVISION
Wichita, Kansas

8

STATE PLUGGING REPORT
J. W. GIBSON WELL SERVICE COMPANY

15-071-20319-0000

Well Name CHECK A-4

Location 11-165-43W

Operator TXO

This well was filled with Wt. 9.2 Mud.

50 sacks were put @ 2400

50 AT 1500
50 AT 460 sacks were put at the bottom of surface pipe and

10 sacks at the top of the surface pipe.

Yes No Steel cap was put on surface casing.

To my knowledge, no junk was left in the hole.

Remarks: _____

Plugging orders were received from JERRY DAMRON

Signed,

J. W. GIBSON-WELL-SERVICE COMPANY

Dale Corbrey

TIME: 9:00 A.M. P.M.

DATE: 5-6-84

RECEIVED
STATE CORPORATION COMMISSION

JUN 06 1984

CONSERVATION DIVISION
Wichita, Kansas