

1080277

TO: STATE CORPORATION COMMISSION

API NUMBER 15-071-20,196-0000  
~~SW NE~~ SEC. 11, T 16 S, R 43 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

10-19

LEASE NAME EDSALL E WELL # 4

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY 170-79

OPERATOR LICENSE # 3273

WELL TOTAL DEPTH 5255 FEET

OPERATOR: HERMAN L. LOEB

PRODUCTION CSG: SIZE 5 1/2" @ 5255' WITH 120 SX

NAME AND PO BOX 524

SURFACE CASING: SIZE 8 5/8" @ 482' WITH 450 SX

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR MULL DRILLING COMPANY INC LICENSE NUMBER 5144

ADDRESS PO BOX 2758 WICHITA, KS 67201-2758

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 19 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM M.L. COX

(COMPANY NAME) MULL DRILLING COMPANY INC. (PHONE) 316-264-6366

WERE: PERFS AT 5140-58. DV @ 2823' WITH 150 SX LITE.

ON 10-18-99 SET CIBP @ 5090' WITH 2 SX CEMENT. SET CIBP @ 2000'. LOADED HOLE. PERFORATED

AT 1950'. RAN TUBING IN HOLE. ON 10-19-99 SET @ 1980'. PUMPED 80 SX CEMENT 200# HULLS AND

100 SX CEMENT. PULLED TUBING TO 600' PUMPED 20 SX CEMENT. PULLED TUBING OUT OF HOLE.

PUMPED DOWN 4 1/2 10 SX CEMENT. MAXIMUM PRESSURE AT 800# AND SHUT IN. PUMPED DOWN 8 5/8 X 5 1/2

ANNULUS 100 SX CEMENT. SHUT IN @ 100#.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 19 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT ON 10-18-99 PEAK WIRELINE SET CIBP @ 5090' WITH 2 SX CEMENT. PEAK

WIRELINE SET CIBP @ 2000'. LOADED HOLE. PERFORATED AT 1950'. RAN TUBING IN HOLE. ON 10-19-

99 SET AT 1980'. PUMPED 80 SX CEMENT 200# HULLS AND 100 SX CEMENT. PULLED TUBING TO 600'.

PUMPED 20 SX CEMENT. PULLED TUBING OUT OF HOLE. PUMPED 4 1/2 10 SX CEMENT. MAXIMUM PRESSURE

AT 800# AND SHUT IN. PUMPED DOWN 8 5/8 X 5 1/2 ANNULUS 100 SX CEMENT. SHUT IN AT 100#.

KANSAS CORPORATION COMMISSION

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED. 10-22-99

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) OCT 22 1999

I (DID) W. Strube 10-22-99 SIGNATURE DATE

DATE

SIGNED

Kevin D Strube

(TECHNICIAN)

FORM CP-213 DIVISION WICHITA, KS

INV. NO. 65772