

1080254

TO:

STATE CORPORATION COMMISSION

7-12

API NUMBER 15-071-20,163-0000

NE NE SE SEC. 11, T 16 S, R 43 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 380 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME EVANS E WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY

OPERATOR LICENSE # 3273

WELL TOTAL DEPTH 5350 173-88 FEET

OPERATOR: HERMAN L. LOEB

PRODUCTION CSG: SIZE 5 1/2" @ 5329' WITH 110SX

NAME AND PO BOX 524

SURFACE CASING: SIZE 8 5/8" @ 578' WITH 590SX

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

Own J.W. Gibson Well Servicing

PLUGGING CONTRACTOR KEY ROCKY MOUNTAIN WELL SERVICE

LICENSE NUMBER 5866

ADDRESS PO BOX 69, CHEYENNE WELLS, CO 82601

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 12 MONTH: 07 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM M.L. COX

(COMPANY NAME) KEY ROCKY MOUNTAIN WELL SERVICE (PHONE) 307-237-7959

WERE: DV @ 2815' WITH 225 SX, PERFS @ 5140-61.5, CIBP @ 5100' WITH 2 SX CEMENT

CIBP @ 5100' WITH 2 SX CEMENT ON TOP.

RAN IN HOLE WITH 5 1/2 R-4 TENSION PACKER TO 2038'. PRESSURED UP TO 300# & HELD. PULLED TUBING

OUT OF HOLE. RAN BOND LOG. BOTTOM CEMENT @ 2860'. TOP CEMENT @ 2383'. SET CIBP @ 2000'.

PERFORATED AT 1950'. RAN IN HOLE WITH TUBING TO 1978'. PUMPED 190 SX CEMENT. CIRCULATED

TO SURFACE. PULL UP TO 600'. PUMPED 25 SX CEMENT. PULLED TUBING OUT OF HOLE. PUMPED 55 SX

CEMENT DOWN 5 1/2. MAXIMUM PSI @ 500#. SHUT IN @ 200#. PUMPED DOWN 8 5/8 X 5 1/2 ANNULUS 100 SX CEMENT

MAXIMUM PSI @ 100#. SHUT IN @ 100#.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 6:30 PM DAY: 12 MONTH: 07 YEAR: 1999

ACTUAL PLUGGING REPORT

SEE ATTACHED PAGE.

RECEIVED

STATE CORPORATION COMMISSION

JUL 28 1999

7-28-99

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE AUG 02 1999

SIGNED Kevin D. Strube
(TECHNICIAN)

FORM CP-2/3

INV. NO. 60085

(2)

15-071-20163-0000
ACTUAL PLUGGING REPORT FOR EVANS E #1 GREELEY COUNTY

CIBP @ 5100' with 2 sx cement on top.

Key Well Service ran in hole with 5½ R-4 tension packer to 2038'. Pressured up to 300# and held. Pulled tubing out of hole. Peak Wireline ran bond log. Bottom cement at 2860'. Top cement at 2383'. Set CIBP at 2000'. Perforated at 1950'. Ran in hole with tubing to 1978'. Allied pumped 190 sx cement. Circulated to surface. Pull up to 600'. Pumped 25 sx cement. Pulled tubing out of hole. Pumped 55 sx cement down 5½. Maximum psi @ 500#. Shut in @ 200#. Pumped down 8⅝ x 5½ annulus 100 sx cement. Maximum psi @ 100#. Shut in at 100#.

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1990

CONSERVATION DIVISION
Wichita, Kansas