

To: 1 031493 3-10
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-071-20,310-0002
NWSE, SEC. 11, T 16 S, R 43 @ E
2310 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License 30689
Operator: MARATHON OIL CO.
Name & Address 1501 STAMPEDE Ave
Cody, Wyoming
82414-4721

Lease Name EVANS E Well 6
County Greeley 192.25
Well Total Depth 5300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 459

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Gibson Well Service License Number 5866
Address 7400 E. ORCHARD R EAGLEWOOD, CO. 80111

Company to plug at: Hour: 11:00 AM Day: 13 Month: 3 Year: 19 98

Plugging proposal received from RODNEY MEALON

(company name) MARATHON OIL CO. (phone) 307-587-4961

Perfs: 5 1/2" @ 5300' w/250sx. PBTD @ 5262 Perfs @ 5158-5178 w 2SPF

Perfs SANDED w/ 250' SAND - Hole in casing @ 2300'

1st set CIBP @ 2100' Perforate casing @ 1650' - circulate cement to Surface.

Plugging Proposal Received by Steve Dumont (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11:00 AM Day: 16 Month: 3 Year: 19 98

ACTUAL PLUGGING REPORT 1st Set CIBP @ 2100' - Perf. Casing @ 2100' - mix & pump 300sx CLASS II cement - NO circulation - Temp survey TOC @ 1590' in & out of casing -

2nd perf casing @ 1000' & circulated cement to surface w/ 180sx

Class II

1st plug was witnessed by Kevin Strube

Remarks: Cement by Gibson Well Service Class II

INVOICED

I (did / did not) observe this plugging.

DATE 3-17-98

INV. NO. 50264

Signed Steve Dumont (TECHNICIAN)

3-17-98 RECEIVED KANSAS CORP COMM