

1 060218

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,603-0000
SE NE NW NE, SEC. 2, T 18 S, R 43 W/X
750 feet from N & section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30606
Operator: Murfin/Axem/DCX
Name & Address: 250 N. Water, Ste. 300
Wichita, KS 67202

Lease Name Bobcat Well # 2-2
County Greeley
Well Total Depth 5290 171.93 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 313

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 8:45 p.m. Day: 21 Month: 1 Year: 1994

Plugging proposal received from Ed McKenna
(company name) Murfin Drilling Company (phone) 316-267-3241

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2648-85'
1st plug at 2750' with 50 sx cement, 2nd plug at 1800' with 50 sx cement,
3rd plug at 900' with 50 sx cement, 4th plug at 350' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30 a.m. Day: 22 Month: 1 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 2750' with 50. sx cement,

2nd plug at 1800' with 50 sx cement, 3rd plug at 900' with 50sx cement,
4th plug at 350' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.
7th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 10 1994
2-10-94
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

DATE (M/D/Y) FEB 11 1994 observe this plugging.

INV. NO. 39921

Signed Case Morris (TECHNICIAN)

EFFECTIVE DATE: 7-21-93
DISTRICT #
SGA7 Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL

071-20,603-0000

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date July 29, 1993
month day year
Spot SE NE NW NE Sec 2 Twp 18 S. Rg 43 East
West

OPERATOR: License # 30606
Name: Murfin/Axem/DEX
Address: 250 N. Water, Suite 300
City/State/Zip: Wichita, Ks. 67202
Contact Person: Scott Robinson
Phone: 316-267-3241

CONTRACTOR: License #: 30606
Name: Murfin Drilling Company, Inc.

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield ... Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal ... Wildcat ... Cable
... Seismic: ... # of Holes ... Other
If OWWO: old well information as follows:
Operator: ...
Well Name: ...
Comp. Date: ... Old Total Depth

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth: ...
Bottom Hole Location: ...

990 feet from South / North line of Section
750 feet from East / West line of Section
IS SECTION REGULAR X IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)
County: Greeley
Lease Name: Bobcat Well #: 2-2
Field Name: Moore-Johnson Extension
Is this a Prorated/Spaced Field? X yes ... no
Target Formation(s): Morrow
Nearest lease or unit boundary: ...
Ground Surface Elevation: Est 3895 3912 feet MSL
Water well within one-quarter mile: ... yes X no
Public water supply well within one mile: ... yes X no
Depth to bottom of fresh water: 60' 1700'
Depth to bottom of usable water: ...
Surface Pipe by Alternate: ... 1 X 2
Length of Surface Pipe Planned to be set: ... 200'
Length of Conductor pipe required: N/A
Projected Total Depth: 5350
Formation at Total Depth: Miss
Water Source for Drilling Operations: ... well ... farm pond X other
DWR Permit #: ...
Will Cores Be Taken?: ... yes X no
If yes, proposed zone: ... 200' Alt. II Req.

Exp. 1/16/94

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Ed Mc Kenney
SPUD DATE 1-12-94 INIT. SM
LENGTH SURFACE PLANNED 300
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 7/8 @ 312 CONDUCTOR
ANHYDRITE T- 26 7/8 B- 26 2 1/2 ELEVATION
TD 5290 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ No G⁴ Ft. W/ SX
Anhydrite Base @ 2750 Ft. W/ 50 SX
1/2 Base Anyh. @ 1800 Ft. W/ 50 SX
1/2, 1/2 Plug @ 900 Ft. W/ 50 SX
Bottom Surface @ 350 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond
Hauling
TECHNICIAN CM DATE 1-21-94
TYPE OF CEMENT 60/40 62 1/4 # F₂
STARTING TIME : (AM/PM) DATE
COMPLETION TIME 2:42 (AM/PM) DATE 1-22
3:30 AM 1-22
CEMENT COMPANY Alled

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1994

CONSERVATION DIVISION
Wichita, Kansas