



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mack Oil Company

Complete Address 812 Union Center, Wichita, Kansas

Lease Name Bailey Well No. 1

Location C NE SE Sec. 36 Twp. 20 Rge. (E) (W) 23

County Ness Total Depth 4501'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 4:50 A Day 9 Month 4 Year 1975

The above well was plugged as follows:

RTD 4501' 8 5/8 csg set 362' cwc 225 sk. Cmt. Mat. 50-50 poz cem. 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 4/15/75

INV. NO. 1161-W