

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION
OCT 2 1962
CONSERVATION DIVISION
Wichita, Kansas
10-02-62Operator's Full Name Union Texas Petroleum Co.Complete Address: Drawer D, Great Bend, Ks.Lease Name M.P. Sleight Well No. 5-Location NW-SW-NE Sec. 15 Twp. 21 Rge. 3 (E) (H)County Marion Total Depth 2876'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Forbes Casing Pulling Co.Address: Box 221 Great Bend, Ks. License No. 49Operation Completed: Hour 3 PM Day 29 Month 9 Year 1962

The Above well was plugged as follows:

Filled hole with sand from TD 2876' back to
2850'. Ran 5" cement with dump bailer. Shot
off & pulled 5 1/2" casing. Filled hole with mud
from 2780' back to 155'. Set 15' rock bridge & filled
hole from 140' back to zero with ready mix cement
8 5/8" surface pipe & cement 4' below ground level

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Eric Myer
Well Plugging SupervisorDATE 10-2-62INV. NO. 6338-E