

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 135 - 21,304 - 0000 (of this well)

Operator's Full Name Kaiser-Francis Oil Co.

Complete Address Box 35528, Tulsa, Oklahoma

Lease Name Petersilie "I" Well No. 1

Location NW SE SW Sec. 1 Twp. 20 Rge. (E) (W) 24

County Ness Total Depth 4442'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Co. Tools

Address      License No.     

Operation Completed: Hour 9:30 A Day 7 Month 4 Year 1977

The above well was plugged as follows:

RTD 4442' 8 5/8 csg set 641' cwc Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 660' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

APR 08 1977

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4-8-77

INV. NO. 4939-W

Signed: Leon Massey  
Well Plugging Supervisor