

15.135-20313-0000

Form CP-3
Rev. 6-4-68

KANSAS

Handwritten initials

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Palomino
Palomino Petroleum

Complete Address 304 Insurance Bldg., Wichita, Kansas

Lease Name Maranville "B" Well-No. 3

Location C NW NW Sec. 13 Twp. 20 Rge. (E) (W) 23

County Ness Total Depth 4348'
~~4378'~~

Abandoned Oil Well Gas Well Input Well SWD Well D & AXX

Other well as hereafter indicated

Plugging Contractor Hellar Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 11:15A Day 23 Month 1 Year 1970

The above well was plugged as follows:

RTD 4378' 8 5/8 csg set at 290' cwc Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Leo J. Messer*
Well Plugging Supervisor

INVOICED

DATE 1/26/70
INV. NO. 1308-W