

15-135-30231-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Shell Oil Company

Complete Address: 1200 First Nat'l Bldg., Oklahoma City Oklahoma

Lease Name Maranville Well No. 2-13

Location C SW SW Sec. 13 Twp. 20 Rge. 23 (E) (W) X

County Ness Total Depth 4370

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling Co.

Address: Great Bend Kansas License No.

Operation Completed: Hour 12 P Day 14 Month 7 Year 1966

The Above well was plugged as follows:

RTD 4370 8 5/8 set at 250 cwc 185 sc

Gunned pits, circulated heavy mud, set cementing plug at 540 and displaced

25 sc cement thru drill pipe. Heavy mud to 250 Ft. set cementing plug and

displaced 20 sc cement thru drill pipe. Heavy mud to 40 Ft. set cementing

plug, 1/3 sc hulls and 10 sc cement to base of celler. Plugged rat hole with

2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. J. Messer
Well Plugging Supervisor

DATE 7/18/66

INV. NO. 3583-W