

*AP*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 1 1971  
CONSERVATION DIVISION  
Wichita, Kansas

*J. Lewis Beck*  
~~J. P. Roberts~~  
~~Assistant Director~~ *Administrator*  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Co. & Southwest Petro - Chem

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Maranville "A" Well No. 3

Location SW SE NW Sec. 13 Twp. 20 Rge.        (E)        (W) 23

County Ness Total Depth 4236

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated:       

Plugging Contractor: Pickrell Drlg.

Address: Wichita, Kansas License No.       

Operation Completed: Hour 4:25 P Day 29 Month 1 Year 1970

The Above well was plugged as follows:

RTD 4236' 8 5/8 csg set at 255' cwc Cmt. Mat. 85 sk reg poz 6%

Gunned pits, circulated heavy mud, set cementing plug at 420' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Geo F. Mussey*  
Well Plugging Supervisor

DATE 2-1-71

INV. NO. 3293-W