

KANSAS

Form CP-3
RECEIVED
Rev. 6-4-68
STATE CORPORATION COMMISSION

NOV - 2 1978

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135-38176-0000 (of this well)

Operator's Full Name Mull Drilling Co., Inc.

Complete Address 221 N. Main, Suite 300, Wichita, Kansas 67202

Lease Name Whitley Well No. 1

Location C NE SE Sec. 13 Twp. 20 Rge. (E) (W) 23

County Ness Total Depth 4352

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargent Casing Pulling

Address Liberal, Kansas License No. 511

Operation Completed: Hour 7 P Day 31 Month 10 Year 1978

The above well was plugged as follows:

Total Depth 4352' 8 5/8 csg set 245' cwc

4 1/2 csg set 4340' cw 125 sk cem.

pumped down 4 1/2 csg-W/30 sk cem. Top of cement 3400'.

Cutoff & recovered 3144' of 4 1/2 csg.

Mixed & pumped down 8 5/8 csg with 16 sk gel & water -followed with 80 sk cement-

displaced with 4 sk gel & water -and capped with 20 sk cem. FPP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 11-3-78
INV. NO. 8458.0