

15-135-3470-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Leben Drilling, Inc.

Complete Address: P. O. Box 486 Great Bend, Kansas

Lease Name Petersilie Well No. C-1

Location NE SW SW Sec. 11 Twp. 20 Rge. 24 (E) (W) X

County Ness Total Depth 4471

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knights Csg., Plg., Co.

Address: Chase, Kansas License No. 436

Operation Completed: Hour 10 A Day 18 Month 6 Year 1966

The Above well was plugged as follows:

Total Depth 4471 8 5/8 at 260 cw 150 sc. 5 1/2 at 4440 cw 100 sc.

Filled with sand to 4425 and dumped 5 sc cement with dump bailer.

Circulated 25 sax Gel thru 5 1/2 csg. at 550 Ft. Displaced 30 sax cement

thru 5 1/2 csg. at 500 Ft. Hvy mud to 240 Ft. and displaced 25 sc. cement

thru 5 1/2 csg. Heavy mud to 40 Ft. Set 10 Ft. rock bridge and filled to

surface with 10 sax cement.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED JUN 22 1966

Signed: Leo Massey
Well Plugging Supervisor

DATE 6/22/66 CONSERVATION DIVISION
Wichita, Kansas
INV. NO. 3448-W