

15-135-20968-0000

Form CP-3
Rev. 6-4-68

~~KANSAS~~

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name The National Oil Co.
Complete Address Suite 550, O. W. Garvey Bldg., Wichita, Kansas
Lease Name Rothe Well No. 1
Location C NW SE SE Sec. 10 Twp. 20 Rge. (E) (W) 24
County Ness Total Depth 4464'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor H-30 Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour ~~15:30~~ Day 20 Month 11 Year 1974

The above well was plugged as follows:

RTD-4465' 8 5/8 csg set at 203' cwc Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.
Heavy mud to 185' & set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set
solid bridge & 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 11/25/74
INV. NO. 346-0