

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW SW SW

SEC. 11 TWP. 20 RGE. 24

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Petersilie

Operator Flynn Oil Co Address 809 Thompson Bldg Tulsa, Okla

Field \_\_\_\_\_ County Ness

Total Depth 4510 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 254' circulated with cement - 5 1/2" at 4437' with  
100 sax behind - plugged back to 4351 with cement - top perf.,  
4320'.

Filled with chat to 4310', set 5 sax cement with dump bailer,  
pulled 5 1/2", filled hole with mud to 250', set rock bridge and  
15 sax cement, filled with mud to 35', set rock and 10 sax cement  
to 0'.

*FL*

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 29 1951  
CONSERVATION DIVISION  
Wichita, Kansas

District Conservation Agent

Date 8-27-51

C. D. STOUGH

PLUGGING  
FILE SEC 11 TWP. 20 R 24W BY  
BOOK PAGE 106 LINE 19

*E. Perry*