

15-135-20068-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 507 4th Nat'l Bank Bldg. Wichita, Kansas

Lease Name Schmidt-"J" Well No. 1

Location C SW SW Sec. 5 Twp. 20 Rge. 24 (E) (W) X

County Ness Total Depth 4430

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co Tools

Address: License No.

Operation Completed: Hour 3:30 P Day 11 Month 10 Year 1967

The Above well was plugged as follows:

RTD 4430' 8 5/8 csg set at 257' cwc 160 sc.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 250' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10/16/67
INV. NO. 6502-W