

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 29 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name R. G. Smith, 15071-20006-0000

Complete Address: 602 Rule Building, Wichita, Kansas.

Lease Name Evans Well No. 1

Location NE-NE-SE Sec. 11 Twp. 16 Rge. (E) (W) 43

County Greeley Total Depth 5574

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Rine Drilling Company,

Address: 420 Union Center Bldg., Wichita, Kansas. License No.

Operation Completed: Hour 1:15AM Day 25 Month 4 Year 1969

The Above well was plugged as follows:

357'--8 5/8" Surface cssing, cement circulated with 360 Sx.

Circulated hole with heavy mud. Pulled DP to 1575' and displaced 100 Sx. cement thru

DP from 1575' to 1250'. Pulled DP to 370' and displaced 25 Sx. cement thru DP from

370' to 295'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. B. Dickole

Well Plugging Supervisor

DATE 4/29/69

INV. NO. 9674-W