

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

JAN 16 1978

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Cain of Strata Drlg. has this

date requested permission to plug the following described well:

Mr. Cain guarantees payment of the plugging fee.

Operator's full Name: Kinderhook Oil & Gas, Inc.

Complete Address: 4608 Boulevard Place, Des Moines, Iowa

Lease Name: Strobel "A" Well No. 1

Location: 150°N & 50°W C SW NW Sec. 19 Twp. 20 Rge. (E)(W) 23

County: Ness Total Depth 4381' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Cain was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 550' thru drill
pipe. Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent