

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. WALKER of RAINS-Williamson has this date requested permission to plug the following described well:

Mr. WALKER guarantees payment of the plugging fee.

Operator's full Name: Mull DICE, Co. Inc.

Complete Address: 1625 Wichita Plaza Wichita, Kansas

Lease Name: Whitley Well No. 3

Location: N-SW-SF Sec. 13 Twp. 20 Rge. 23 (E)(W) X

County Ness Total Depth 4353 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. WALKER was instructed to plug the well as follows:

Jet pits circulate hole with heavy mud, set cementing plug at 540 ft.,
and displace 25 sack cement thru drill pipe, heavy mud to 240 ft.,
set cementing plug and displace 20 sack cement thru drill pipe, heavy
mud to 40 ft., set cementing plug, 1/2 sack balls and 10 sack cement,
cementing to base of cellar. Plug rat hole with two sack cement.

RECEIVED Very truly yours,
STATE CORPORATION COMMISSION

MAY 26 1966 Leo Massey
Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas