

15.135.20968 0000

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 22 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Cameran of H-30 rlg. has this

date requested permission to plug the following described well:

Mr. Cameran guarantees payment of the plugging fee.

Operator's full Name: The National Oil Co.

Complete Address: Suite 550, O. W. Garvey Bldg., Wichita, Ks.

Lease Name: Rothe Well No. 1

Location: C NW SE SE Sec. 10 Twp. 20 Rge. (E) (W) 24

County: Ness Total Depth 4465' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Cameran was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set 70 sk cmt plug at 660' thru drill  
pipe. Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud  
to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo L. Massey  
Conservation Division Agent