



KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

1084958

Form CDP-1
May 2010
Form must be Typed

APPLICATION FOR SURFACE PIT

Submit in Duplicate

Operator Name: Farmer, John O., Inc.		License Number: 5135	
Operator Address: 370 W WICHITA AVE		PO BOX 352 RUSSELL KS 67665	
Contact Person: Marge Schulte		Phone Number: 785-483-3144	
Lease Name & Well No.: KUHNLE 11		Pit Location (QQQQ): ____ NE ____ NW ____ SW Sec. <u>4</u> Twp. <u>15</u> R. <u>12</u> ☐ East ☒ West <u>2310</u> Feet from ☐ North / ☒ South Line of Section <u>990</u> Feet from ☐ East / ☒ West Line of Section Russell County	
Type of Pit: ☐ Emergency Pit ☐ Burn Pit ☐ Settling Pit ☐ Drilling Pit ☒ Workover Pit ☐ Haul-Off Pit (If WP Supply API No or Year Drilled) 15-167-05180-00-00	Pit is: ☐ Proposed ☒ Existing If Existing, date constructed: 6/13/2012 Pit capacity: 337 (bbls)		
Is the pit located in a Sensitive Ground Water Area? ☐ Yes ☒ No		Chloride concentration: _____ mg/l (For Emergency Pits and Settling Pits only)	
Is the bottom below ground level? ☒ Yes ☐ No	Artificial Liner? ☒ Yes ☐ No	How is the pit lined if a plastic liner is not used?	
Pit dimensions (all but working pits): <u>30</u> Length (feet) <u>9</u> Width (feet) ☐ N/A: Steel Pits Depth from ground level to deepest point: <u>7</u> (feet) ☐ No Pit			
If the pit is lined give a brief description of the liner material, thickness and installation procedure. Pit dug and plastic liner inserted.		Describe procedures for periodic maintenance and determining liner integrity, including any special monitoring. Test water level in pit to determine liner integrity.	
Distance to nearest water well within one-mile of pit: <u>4336</u> feet Depth of water well <u>15</u> feet		Depth to shallowest fresh water <u>10</u> feet. Source of information: ☐ measured ☐ well owner ☐ electric log ☒ KDWR	
Emergency, Settling and Burn Pits ONLY: Producing Formation: _____ Number of producing wells on lease: _____ Barrels of fluid produced daily: _____ Does the slope from the tank battery allow all spilled fluids to flow into the pit? ☐ Yes ☐ No		Drilling, Workover and Haul-Off Pits ONLY: Type of material utilized in drilling/workover: <u>salt water</u> Number of working pits to be utilized: <u>1</u> Abandonment procedure: <u>Wait for any solids to settle, haul water (will file CDP-5 if necessary) or allow to evaporate, remove liner and backfill pit.</u> Drill pits must be closed within 365 days of spud date.	
Submitted Electronically			

KCC OFFICE USE ONLY

☒ Liner ☐ Steel Pit ☐ RFAC ☐ RFAS

Date Received: 06/19/2012 Permit Number: 15-167-05180-00-00 Permit Date: 06/22/2012 Lease Inspection: ☒ Yes ☐ No

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Conservation Division
Finney State Office Building
130 S. Market, Rm. 2078
Wichita, KS 67202-3802



Phone: 316-337-6200
Fax: 316-337-6211
<http://kcc.ks.gov/>

Mark Sievers, Chairman
Ward Loyd, Commissioner
Thomas E. Wright, Commissioner

Sam Brownback, Governor

June 22, 2012

Marge Schulte
Farmer, John O., Inc.
370 W WICHITA AVE
PO BOX 352
RUSSELL, KS 67665-2635

Re: Drilling Pit Application
KUHNLE 11
Sec.04-15S-12W
Russell County, Kansas

Dear Marge Schulte:

District staff has inspected the location and has determined that an unsealed condition will present a pollution threat to water resources.

District staff has recommended that the Workover pit be lined. If a plastic liner is to be used it must have a minimum thickness of 10 mil. Integrity of the liner must be maintained at all times.

NO completion fluids or non-exempt wastes shall be placed in the Workover pit.

The free fluids in the Workover pit should be removed as soon as practical after drilling operations have ceased. The fluids should be taken to an authorized disposal well. Please call the District Office at (785) 625-0550 when the fluids have been removed. Please file form CDP-5 (August 2008), Exploration and Production Waste Transfer, through KOLAR within 30 days of fluid removal.

If you have any questions or concerns please feel free to contact the District Office at (785) 625-0550.