

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

RECEIVED
STATE CORPORATION COMMISSION
NOV 08 1994
CONSERVATION DIVISION
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-135-20,406-000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 6/95-

WELL OPERATOR Pickrell Drilling Co., Inc. KCC LICENSE # 5123
(owner/company name) (operator's)

ADDRESS 110 N. Market, Suite 205 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-8427

LEASE Betz "C" WELL# 3 SEC. 13 T. 20S R. 23 (East/West)

150' W ^{Qf} SE - NE SPOT LOCATION/0000 COUNTY Ness

3300 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

810 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 267 CEMENTED WITH 150 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 4334 CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: B.P. @ 4276, Marm. Perfs. 4226-4230

ELEVATION 2221 KB T.D. 4340 PBSD 4387 ANHYDRITE DEPTH 1412 (+809)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Use 60/40 Poz cement w/ 6% gel. Pump 200# hulls, 25 ex. cement, 28 bbls. of gel mud (140 ex), 130 ex of cement (theor.= 126 ex). Continue cement to pressure up on well and shut in with pressure. After plugging long string, tie into 8 5/8 x 5 1/2 annulus and attempt to pump in cement.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ed Mondero PHONE# (913) 798-2430

ADDRESS P.O. Box 375 City/State Ness City, Kansas 67560

PLUGGING CONTRACTOR Allied Cementing Company KCC LICENSE # _____
(company name) (contractor's)

ADDRESS P.O. Box 628, Great Bend, KS 67530 PHONE # (316) 793-5861

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 11-15-94

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11-07-94 AUTHORIZED OPERATOR/AGENT: Jack Gurley
(Jack Gurley)



Kansas Corporation Commission

Joan Finney, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

November 8, 1994

Pickrell Drilling Company Inc
110 N Market Suite 205
Wichita KS 67202

Betz "C" #3
API 15-135-20,406-0000
3300 FSL 810 FEL
Sec. 13-20S-23W
Ness County

Dear Ed Mondero,


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760