

RECEIVED

OCT 25 2002

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-135-00057-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Whitetail Crude Inc. KCC LICENSE # 31627
(owner/company name) (operator's)

ADDRESS P.O., Box 544 CITY Ness City

STATE KS ZIP CODE 67560 CONTACT PHONE # (785) 798-3641

LEASE Lundy-Hair Lease WELL # 1 SEC. 4 T. 20 R. 24 (East West)

W1/4 - NW1/4 - W1/4 - NE1/4 SPOT LOCATION/0000 COUNTY Ness

660 FEET (in exact footage) FROM S (11) (circle one) LINE OF SECTION (NOT Lease Line)

410 FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/EHHR WELL DOCKET#

CONDUCTOR CASING SIZE 0 SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 270 CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 4470 CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4401-02 4410-14

ELEVATION 2328 T.D. 4473 PBTD 4424 ANHYDRITE DEPTH 1650
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE
Packer in hole on bottom, leak at 3400 ft.

PROPOSED METHOD OF PLUGGING Sand off bottom 50 ft. above the packer, dump four

sacks with a dump bailer, pump 50 sacks to 2000 ft., pressure up casing,

if holds pressure will shoot off casing and spot 80 sks at 750 ft, 40 sks at 300 ft

(if additional space is needed attach separate page) 10sks at 40 ft.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes

~~if not explain why?~~ - footnote - Casing was squeezed at 1300 ft in 1977 w/150 sks.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mike J. Fritzler PHONE# () 785-798-3641

ADDRESS P.O. Box 544 City/State Ness City, KS 67560

PLUGGING CONTRACTOR Swift Services Inc. KCC LICENSE # 32382 ^{10/02}
(company name) (contractor's)

ADDRESS P.O. Box 466, Ness City KS 67560 PHONE # () 785-798-2300

PROPOSED DATE AND HOUR OF PLUGGING (if known?) As soon as possible - 10/28/02

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-116) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 10/24/02 AUTHORIZED OPERATOR/AGENT: Mike J. Fritzler
(signature)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Whitetail Crude, Inc
N Hwy 283
PO Box 544
Ness City, KS 67560-544

October 30, 2002

Re: LUNDY-HAIR #1
API 15-135-00057-00-00
CNWNE 4-20S-24W, 660 FNL 410 FWL
NESS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888

Sincerely
A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor