

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,887-0000

LEASE NAME Jedlicka

WELL NUMBER 1

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 33 TWP. 20 RGE. 23 (E or W)

COUNTY Ness

Date Well Completed 8-20-85

Plugging Commenced 8-20-85

Plugging Completed 8-20-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Vincent Oil Corporation

ADDRESS 125 N. Market - Suite 1110, Wichita, Kansas 67202

PHONE# (316) 262-3573 OPERATORS LICENSE NO. 5004

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|-----|--------|---------|------------|
| | | 0 | 388 | 8 5/8" | 8-12-85 | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well with 190 sxs 60/40 poz, 2% gel, 3% cc as follows: 1500'-50 sxs; 1200'-80 sxs; 428'-40 sxs; ; 40'-10 sxs solid bridge, rathole-10 sxs. Plug down at 3:15 a.m. on August 20, 1985. Job by Allied Cementing, Ness City.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149


Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124



SUBSCRIBED AND SWORN TO before me this 30th day of August, 19 85

Mary L. Tjaden
Notary Public

My Commission Expires: 3/22/88

RECEIVED
STATE CORPORATION COMMISSION

9-3-85
SEP 3 1985

Form CP-4
Revised 08-84



- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

Oilfield Services, Inc.

DRILLER'S WELL LOG

Jedlicka #1
 C SE NE SE Sec. 33-20S-23W
 Ness County, Kansas
 Commenced: 8-12-85
 Completed: 8-20-85
 API #15-135-22,887-0000
 Operator: Vincent Oil Corporation


| Depth | | Formation | Remarks |
|-------|------|-------------|--|
| From | To | | |
| 0 | 400 | Sand, Shale | Ran 9 joints new, 23#, 8 5/8" surface casing. Set at 388' with 150 sxs lite and 100 sxs Common, 2% gel, 3% cc. Cement did circulate. Plug down at 8:00 p.m. August 12, 1985. Job by Allied Cementing, Ness City. |
| 400 | 834 | Shale | |
| 834 | 1758 | Clay, Shale | |
| 1758 | 1852 | Shale | |
| 1852 | 3245 | Lime, Shale | |
| 3245 | 3490 | Shale | |
| 3490 | 4280 | Lime, Shale | |
| 4280 | 4298 | Lime | |
| 4298 | 4373 | Lime, Shale | |
| 4373 | 4415 | Lime | |
| | | T.D. | RTD 4415' |
| | | | Plugged well with 190 sxs 60/40 poz, 2% gel, 3% cc as follows: 1500'-50 sxs; 1200'-80 sxs; 428'-40 sxs; 40'-10 sxs solid bridge, rathole-10 sxs. Job by Allied of Ness City. Plug down at 3:15 a.m. on August 20, 1985. State Plugger was out of Dodge City, Kansas, Office. |

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

Arnie Little
 ARNIE LITTLE, VICE-PRESIDENT



Mary L. Tjaden
 NOTARY PUBLIC

My Commission Expires:
3/22/88

RECEIVED
 STATE CORPORATION COMMISSION

SEP 3 1985