

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ness County. Sec. 30 Twp. 20S Rge. 23W E.A. -  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_

C-NW SE NE  
Lease Owner Ram Petroleum Corporation  
Lease Name Busch Well No. 1

Office Address 800 Vickers KSB & T Bldg., Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) 67202


Dry Hole

Date Well completed May 21, 1979  
Application for plugging filed Verbal Application 19\_\_  
Application for plugging approved Verbal Approval 19\_\_  
Plugging commenced May 21, 1979  
Plugging completed May 21, 1979  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marvin Schmidt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,400'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	564'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,400 ft. (rotary total depth) to 750 ft. Set plug at 750 ft. and cemented with 60 sacks cement. Filled hole with heavy rotary mud from 750 ft. to 550 ft. Set plug at 550 ft. and cemented with 25 sacks cement. Filled hole with heavy rotary mud from 550 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement. 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing, Inc.  
Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Dean Britting, Agent ~~Employer of owner~~ ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
200 N. Main, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of June, 1979

My commission expires July 25, 1982

Elsie Wilton  
Elsie Wilton Notary Public.  
STATE CORPORATION COMMISSION

JUN - 4 1979

CONSERVATION DIVISION  
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY **Ram Petroleum Corporation**  
FARM **Busch** NO. **1**

SEC **30** T. **20S** R. **23W**  
LOC. **C-MW SE NE**

COUNTY **Ness**

ROTARY TOTAL DEPTH **4,400'**  
COMM. **May 7, 1979** COMP. **May 21, 1979**  
CONTRACTOR **H-30, Inc. (Rig #2)**  
ISSUED **June 1, 1979**

CASING

10 3/4"  
8 5/8" **Set at 564' cemented w/300 lbs cement**  
5 1/2"  
4 1/2"

ELEVATION **2,248' K.B.**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	120'
Shale and Sand	565'
Red Bed and Shale	940'
Sand	1,170'
Shale and Shells	1,200'
Sand and Shale	2,170'
Lime and Shale	2,589'
Shale	2,795'
Lime and Shale	3,145'
Shale	3,300'
Lime and Shale	3,975'
Lime	4,150'
Lime and Shale	4,240'
Lime	4,400'
Rotary Total Depth	4,400'

RECEIVED  
STATE CORPORATION COMMISSION

JUN - 4 1979

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the above and foregoing to be  
a true and correct log of the above described  
well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
\_\_\_\_\_  
Dean Britting

State of Kansas }  
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public  
in and for said county and state this 1st day of  
June, 1979.



*Elsie Willison*  
\_\_\_\_\_  
Elsie Willison - Notary Public

My Commission Expires:  
July 25, 1982