

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,317-0000

LEASE NAME STUM

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 32 TWP. 20 SRGE. 23 (X) or (W)

COUNTY Ness

Date Well Completed 1-9-89

Plugging Commenced 1-9-89 3:00PM

Plugging Completed 1-9-89 4:30 PM

LEASE OPERATOR MORRISON-DIXON OIL OPERATIONS, INC.

ADDRESS One Main Place-Suite 801 Wichita, Ks. 67202

PHONE#(316) 264-9632 OPERATORS LICENSE NO. 03372

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 9, 1989 (date)

by Richard Lacey -- Dan Goodrow on location (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4410'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		surf	260'	8 5/8"	260	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

50 sx. 60/40 Pozmix, 6% Gel @ 1470', 80 sx. 60/40 Pozmix, 6% Gel @ 700',
40 sx. 60/40 Pozmix, 6% Gel @ 290', 10sx 60/40 Pozmix, 6% @ 40', 15 sx. 60/40 Pozmix, 6% Gel
in rathole. Total 195 sx.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. _____

Address Russell, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Morrison-Dixon Oil Operations, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Greg Davidson (Employee of Operator) or (~~Representative~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Greg Davidson

(Address) Greg Davidson
Great Bend, Kansas 67530

STATE CORPORATION COMMISSION

RECEIVED
01-17-89

SUBSCRIBED AND SWORN TO before me this 11th day of January, 19 89



CONSERVATION DIVISION

My Commission Expires 5-20-89

Notary Public

Bessie M. DeWerff

DRILLERS WELL LOG

DATE COMMENCED: 1-2-89
DATE COMPLETED: 1-9-89

MORRISON-DIXON OIL OPERATIONS
STUM #1
C NW SE Sec. 32-20S-23W
Ness County, Kansas

0 - 260 Sand & Clay
260 -1840 Clay & Shale
1840 -2485 Lime & Shale
2485 -2676 Lime
2676 -3410 Lime
3410 -3635 Shale & Lime
3635 -3770 Lime
3770 -4025 Lime & Shale
4025 -4089 Lime
4089 -4410 Lime & Shale
4410 R.T.D

Elevation: 2227 GR 2232 KB

FORMATION DATA:

Anhydrite 1438-1476
Heebner 3690
Lansing 3736
Hushpuckney 4036
Marmathon 4124
Ft. Scott 4271
Cherokee 4297
Mississippi 4393
R.T.D. 4410

SURFACE CASING:

8 5/8" set at 260' W/150 sx.
60/40 Pozmix, 2% Gel, 3% CC


A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 12th day of January, 1989.



Bessie M. Deweff
Notary Public: Bessie M. Deweff

My Commission expires: 5-20-89

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1989

CONSERVATION DIVISION
Wichita, Kansas