


Give All Information Completely
Make Required Affidavit
Mail & Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-115-19269-0000
Form CP-4

NORTH

Locate well correctly on above
Section Plat

Marion County. Sec. 19 Twp. 21S Rge. 3 (E) ~~34W~~
Location as "NE/CNW&SW&" or footage from lines NW SW NE
Lease Own. Union Texas Petroleum Corporation
Lease Name K. P. Slocombe Well No. 5
Office Address Drawer D, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Jan. 24, 19 57
Application for plugging filed Sept. 26, 19 62
Application for plugging approved Sept. 27, 19 62
Plugging commenced Sept. 27, 19 62
Plugging completed Sept. 29, 19 62
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production Jan. 27, 19 62
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation Depth to top Bottom Total Depth of Well 2850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	122	none
				5 1/2	none	1701

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cleaned out cellar and sanded to 2830'. Dumped 5 sacks cement and worked pipe. Worked pipe and shot at 2200', 2100', 2000', 1900', 1800', 1690'. Pulled pipe. Pulled pipe and plugged with mud. Bailed hole to 150' and built rock bridge. Dumped 2 sacks cement and capped well with 2 yds. ready-mix. Cleaned and doped and put on pector.

RECEIVED
OCT 1 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

G. M. Dougherty (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Drawer D, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of October, 19 62

Eather L. Koch

Notary Public.

My commission expires Feb. 7, 1966

15-15-19269-0000

DRILLERS' LOG

Company: Anderson-Prichard Oil Corporation

Farm Name: Slocombe

Well No. 5

NW SW NE

Sec. 19, Twp. 21S, Rge. 3E,

County: Marion,
Kansas

Total Depth: 2876'

Comm: 1/6/57 Comp: 1/13/57

Contractor: Glenn W. Peel

Elevation:

Production:

Casing: 8 5/8" @ 122' cem.
5 1/2" @ 2875' cem.

Figures below indicate bottoms of formations:

Surface soils	0 -	70
Lime		330
Lime and shale		670
Shale		1300
Lime and shale		1780
Sand and shale		1975
Lime and shale		2210
Lime		2570
Lime and chert		2690
Lime		2705
Shale and lime		2735
Shale		2836
H. Lime		2864
Shale		2876
Total Depth		2876

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEEL

BY: Al H. Smith

SUBSCRIBED AND SWORN to before me this 15th day of January, 1957.

My commission expires: April 27, 1960

Ruth Black
Notary Public

RECEIVED
STATE OF KANSAS COMMISSION

SEP 27 1962

CONSERVATION DIVISION
Wichita, Kansas