

15.135.21015.0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. _____ Twp. _____ Rge. _____ (E) _____ (W)

Location as "NE/CNW/SW" or footage from lines _____

Lease Owner Kaiser Francis

Lease Name Petersilie "JN" Well No. 1

Office Address 4120 East 51st Street, Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed _____ 19 _____

Application for plugging filed _____ 19 _____

Application for plugging approved _____ 19 _____

Plugging commenced May 19 19 75

Plugging completed May 19 19 75

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	401'	Ø

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Well plugged in the following manner, as per instruction Mr. Massey, State plugger

Drilling mud and gel from 560' to TD
80 sacks of pozmix 6% from 320' to 560'
8 sacks gel and water from 80' to 320'
20 sacks cement from 0' to 80'

Material used: 10 sacks gel with 2 sacks hulls
Plug container
80 sacks pozmix cement
8 sacks gel
20 sacks cement.

05-29-75

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing

Address Great Bend, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

Herbert J. Miller (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herbert J. Miller
4120 E. 51st St., Tulsa, Oklahoma 74135
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of May, 19 75

My commission expires 6/12/76

G. A. Weber
Notary Public.

15-135-21015-0000
 KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Francis Oil & Gas, Inc.


SEC. 1 T. 20S R. 24W
 LOC. S/2 SW/4 SE/4

FARM Petersilie "J" NO. 1

TOTAL DEPTH 4,467'
 COMM. March 4, 1975
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED

COMP. March 15, 1975

COUNTY Ness
 KANSAS



CASING

20	10		
15	8	-5/8" 401' cemented w/250 sxs cement	ELEVATION 2,331' KB
12	6		
13	5		

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale, Sand, Clay and Post Rock	403'
Shale and Red Bed	1,050'
Sand	1,310'
Shale and Lime	1,595'
Anhydrite	1,672'
Shale	2,214'
Shale and Lime	2,700'
Lime	3,068'
Lime and Shale	3,370'
Lime	4,467'
Rotary Total Depth	4,467'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling report.

H-30, INC.

Dean Britting
 Dean Britting

State of Kansas)
) ss:
 County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 18th. day of March, 1975.

Elsie Willison
 Elsie Willison -Notary Public

My Commission Expires:

June 30, 1978

