

15-135-20729-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County, Sec. 1 Twp. 20S Rge. (E) 24 (W)

Location as "NE/CNW4SW4" or footage from lines C/NE SE

Lease Owner Thunderbird Drilling, Inc.

Lease Name Petersilie "F" Well No. 1

Office Address 4328 East Kellogg, P. O. Box 18407, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 3 19 73

Application for plugging filed March 3 19 73

Application for plugging approved March 3 19 73

Plugging commenced March 4 19 73

Plugging completed March 4 19 73

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4460 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	623.42'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole as follows: Plugged at 720' with 50 sacks of 50-50 pozmix ; plugged at 300' with 25 sacks of 50-50 pozmix; plugged at 40' with 10 sacks of 50-50 pozmix. Plug down at 2:30 A. M. March 4, 1973.

RECEIVED
STATE CORPORATION COMMISSION

MAR 9 1973

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor (If additional description is necessary, use BACK of this sheet) Strata Drilling, Inc.

Address P. O. Box 355, Great Bend, Kansas 67530


STATE OF KANSAS COUNTY OF BARTON ss. Charles W. Steincamp

(employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 6th day of March 19 73

December 14, 1973 Elaine H. Taylor Notary Public.



D R I L L E R S L O G

#1 Petersilie "F"

CASING RECORD:
617.42' of used 8-5/8"
surface casing.

COMPANY: Thunderbird Drilling, Inc.
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/NE SE
Section 1-20S-24W
Ness County, Kansas

TOTAL DEPTH:
4460'

COMMENCED: February 22, 1973
COMPLETED: March 4, 1973

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	40	Ran 617.42' of used 8-5/8" surface casing; set and cemented at 623.42' with 300 sacks of common cement, 2% gel and 3% C. C. Plug down at 8:40 A. M. February 23, 1973.
Shale	40	650	
Sand, Shale & Shells	650	750	
Shale	750	1050	
Sand	1050	1260	
Shale	1260	1616	
Anhydrite	1616	1640	
Shale	1640	1850	
Shale w/Sand Streaks	1850	2395	
Shale & Lime	2395	2540	
Lime & Shale	2540	4425	
Lime & Chert	4425	4450	
Dolomite	4450	4460	

ROTARY TOTAL DEPTH: 4460'

Ran electric log

D. & A.

Plugged hole as follows: Plugged at 720' with 50 sacks of 50-50 pozmix; plugged at 300' with 25 sacks of 50-50 pozmix; plugged at 40' with 10 sacks of 50-50 pozmix. Plug down at 2:30 A. M. March 4, 1973.

RECEIVED
STATE CORPORATION COMMISSION
MAR 9 1973
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 6th day of March, 1973.

My Commission Expires:
December 14, 1978

Elaine H. Taylor
Elaine H. Taylor, Notary Public

