

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

15-135-00165-0000

Ness County, Sec. 3 Twp. 20S Rge. (E) 24 (W)
Location as "NE/CNW&SW&" or footage from lines C SE SW
Lease Owner Pickrell Drilling Company
Lease Name Rothe A Well No. 1
Office Address 705 Fourth National Bank Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 12 1961
Application for plugging filed October 12 1961
Application for plugging approved October 12 1961
Plugging commenced October 12 1961
Plugging completed October 12 1961
Reason for abandonment of well or producing formation Dry Hole

NORTH

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4483 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	295'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 240'. Set Plug. Cemented
with 20 sacks cement. Heavy mud to 35'.
Set Plug. Cemented with 10 sacks cement
to bottom of cellar. Plugged rat hole
with 2 sacks cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.
C. W. Sebts (owner or ~~agent~~) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebts
705 Fourth National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of October, 1961

My commission expires September 24, 1962

Maxine Johnson Notary Public.

15-135-00165-0000
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita 2, Kansas
LOCATION: ROTHE A #1 - C SE SW, Sec. 3-20S-24W,
Ness County, Kansas

Rotary Drilling Commenced 9/28/61
Rotary Drilling Completed 10/12/61

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: 295' (6 jts.) 8 5/8" 20# Surface Casing with 155 sacks cement.
Circulated. No oil string run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>Circulated for Samples</u>
40'	Clay	4322'
295'	Shale & Shells	4345'
330'	Shale	4403'
500'	Grey Shale	4410'
755'	Blue Sandy Shale	4420'
973'	Shale & Red Bed	4435'
985'	Blaine	4445'
1060'	Red Bed & Shale	4450'
1325'	Sand	4460'
1595'	Shale & Shells	4483'
1640'	Anhydrite	
2125'	Shale & Shells	
2190'	Lime, Shale & Salt	<u>Slope Test</u>
2540'	Lime & Shale	1640' 0°
2820'	Lime	2540' 0°
3440'	Lime & Shale	3571' 0°
3735'	Lime, Shale & Sand	4345' 0°
3950'	Lime & Shale	
4045'	Lime	<u>S. L. M.</u>
4345'	Lime & Shale	1500'
4450'	Lime, Shale & Chert	2500'
4483'	Lime & Chert R.T.D.	3500'

Oct 24 1961
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By

C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 23rd day of October, 1961, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson
Maxine Johnson Notary Public