


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 13 Twp. 20 Rge. 23W E/W
Location as "NE/CNW/SW" or footage from lines

C NE SE
Lease Owner Mull Drilling Co.
Lease Name Whitley Well No. 1
Office Address Ness City, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Oil
Date Well completed 2-9 1966
Application for plugging filed 10-30 1978
Application for plugging approved 10-30 1978
Plugging commenced 10-30 1978
Plugging completed 11-2 1978
Reason for abandonment of well or producing formation
Depletion

If a producing well is abandoned, date of last production
May 1978

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4344
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 245 | none |
| | | | | 4 1/2 | 4331 | 3131 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Mixed 2 sks. of hulls & 30 sks. of cement plug @ 3400'
Gel. T.D. - 460 Cement 460 - 220 Gel. 220 - 60 Cement 60 - 0

RECEIVED
STATE CORPORATION COMMISSION

DEC - 6 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Sargent's Casing Pulling Service Box 506 Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Robert Wall (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Robert O. Wall
Main 221 - Suite 300 - Wichita, Ks 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of December, 1978

My commission expires



Christina M. Zimmerman
Notary Public.

15-135-38176-0000

Operator: Mull Drilling Co., Inc.
No. 1 Whitley
C NE SE of Sec. 13-20S-23W
Ness County, Kansas

Contractor: Rains & Williamson Oil Co.
Commenced: 12-26-65
Completed: 1-7-66

Remarks: Set 245' of 8-5/8" surface casing, with 200 sacks cement.

Set 4 1/2" 13' off bottom, with 125 sacks 60-40 posmix.

Formations:

| | |
|------------------------|-----------|
| Surface Soil and Sand | 245' |
| Shale | 890' |
| Sand | 1092' |
| Shale | 1235' |
| Red Sed & Shale | 1416' |
| Anhydrite | 1451' |
| Shale & Shells | 2100' |
| Shale & Lime | 2355' |
| Lime & Shale | 2685' |
| Lime | 2793' |
| Shale & Lime | 3083' |
| Lime & Shale | 3250' |
| Shale & Lime | 3405' |
| Lime & Shale | 3741' |
| Lime & Shale & Chalk | 3788' |
| Lime & Shale | 3855' |
| Lime | 3987' |
| Lime & Shale | 4052' |
| Lime | 4344' |
| Rotary Total Depth | 4344' |

RECEIVED
STATE CONSERVATION COMMISSION
NOV - 2 1978
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, This 12th day of January, 1966.

My commission expires: 1-8-68

Shirley Reck
Shirley Reck

