

1 050497

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,294-0000  
145' W of C  
NW NW NE, SEC. 3, T 17 S, R 16 W/R

4950 feet from S section line  
2455 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name Yarmer Well # 1

Operator: Abercrombie Drilling, Inc.

County Rush 116.19

Name & Address 801 Union Center

Well Total Depth 3575 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A x

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 8:00 pm Day: 30 Month: March Year: 1985

Plugging proposal received from Wilmer Dreiling

(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1050' with 50 sx cement

2nd plug at 520' with 70 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:45 pm Day: 30 Month: March Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 1050' with 50 sx cement, 2nd plug at 520' with 70  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface  
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

STATE CORPORATION COMMISSION

APR 12 1985

4-12-85

CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun  
(If additional description is necessary, use BACK of this form.)

INVOICED

(you did not) observe this plugging.

DATE 4-16-85

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 7736

MAY 09 1985

3-35

FORM CP-2/3  
Rev. 01-84