

1 030393

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,287-0000
NW SW SE, SEC. 2, T 17 S, R 16 W/E
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Juno Well # 1

Operator: Thunderbird Drilling, Inc.

County Rush 117.91

Name & Address P. O. Box 18407

Well Total Depth 3628 feet

Wichita, KS 67218

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 346 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor Thunderbird Drilling, Inc. License Number 5131

Address P. O. Box 18407, Wichita, KS 67218

Company to plug at: Hour: 11:00 am Day: 3 Month: April Year: 19 85

Plugging proposal received from Ed Cook

(company name) Thunderbird (phone) 316-685-1441

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1140' with 50 sx cement

2nd plug at 750' with 50 sx cement

3rd plug at 360' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:30 pm Day: 3 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1140' with 50 sx cement, 2nd plug at 750' with 50

sx cement, 3rd plug at 360' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole

with 10 sx cement.

STATE CORPORATION COMMISSION

APR 12 1985
4-12-85

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

(do not) observe this plugging.

INVOICED

DATE 4-18-85

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 7774

4-3