

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-165-30004-00-01

NW/4, Sec. 5, T 17 S, R 16 W/E  
(SWSWNW) feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

\_\_\_\_\_ feet from W/E section line

Operator: FRONTIER OIL CO.  
Name & Address 1720 KANSAS STATE BANK BLDG.  
WICHITA, KS 67202

Lease Name Honderick Well # B-1

County RUSH

Well Total Depth 3610 feet

Conductor Pipe: Size 8 7/8 feet 215'

Surface Casing: Size 4 1/2 feet 3196

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ROCKHOLD ENGINEERING INC License Number 5111

Address Box 698, GREAT BEND, 67530

Company to plug at: Hour: 9 AM Day: 7 Month: 11 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO D. B. PULLEY

(company name) ROCKHOLD (phone) \_\_\_\_\_

were: Sand bottom to 2990 and add 7 sy Comm. Cmt.  
Use 50/50 Pozmix, 4% gel - 3% CC - Pumped  
3 sy hulls, 20 sy gel, 70 sy Cmt. Then 15 sy  
gel, 1 sy hulls, released 8 7/8 plug and finished  
w/100 sy Cmt. Cementing by Sun.

Signed R. B. Arbutson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 AM Day: 7 Month: Nov Year: 1982

ACTUAL PLUGGING REPORT Plugged as ordered.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 08 1982  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: TOP OF PERFS. @ 3040

PBTD @ 3200'

Rec. 2500' of 4 1/2" tubing

I hereby certify that the above plugging instructions were given as herein stated  
and that I (~~did~~ / did not) observe this plugging. Observed by J. H. Dietz

Signed R. B. Arbutson  
(TECHNICIAN)

11-23-82  
1680-W