

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-20598-00-00  
Spot: NWNESW Sec/Twnshp/Rge: 7-17S-16W  
2310 feet from S Section Line, 1350 feet from W Section Line  
Lease/Unit Name: JANSON - A Well Number: 2  
County: RUSH Total Vertical Depth: 3218 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 603 MAIN AVE., STE 500  
KNOXVILLE, TN 37902

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 284 WITH 175 SX CMT \$104.59  
Production: Size 4.5 feet: 3218 WITH 150 SX CMT  
Liner: Size \_\_\_\_\_ feet:

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2001 8:55 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: ED GLASSMAN Company: TENGASCO Phone: (423) 523-1124

Proposed Plugging Method: PUMP 200# & 25 SX CMT ON BOTTOM. FILL WITH 60/40 POZMIX 6% GEL. PUMP 50 SX DOWN BACKSIDE IF NEEDED.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/31/2001 10:40 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 3163'. CEMENTED FROM 1190' TO SURFACE WITH 400 SX CMT. PUMPED 25 SX CMT WITH 200# HULLS TO BOTTOM THROUGH TUBING. PULLED TUBING TO 1200' & PUMP 80 SX CMT. HOLE CIRCULATED. PULLED TUBING AND TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE AND PRESSURED TO 500# AND HELD.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED

NOV 02 2001

KCC WICHITA

INVOICED

NOV 01 2001

DATE 11-2-01

INV. NO. 2002060899

Form 93-73