

1 030896

167-51 577

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,397-0000

NW SW NW, SEC. 10, T 17 S, R 16 W/E

3630 feet from S section line

4950 feet from E section line

Lease Name Maneth Well # 1

County Rush 116.51

Well Total Depth 3585 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 761

TECHNICIAN'S PLUGGING REPORT

Operator License # 7261

Operator: Pate-Dombaugh Petroleum

Name & Address 804 Union Center Building

Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 1:30 a.m. Day: 21 Month: 12 Year: 19 87

Plugging proposal received from Wilmer Dreiling

(company name) Abercrombie Drilling, Inc. (phone) 316-793-8186

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1099-1127'

1st plug at 1110' with 40 sx cement,

2nd plug at 760' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:15 a.m. Day: 21 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1110' with 40 sx cement,

2nd plug at 760' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If you did not observe this plugging.

DATE 1-7-88

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 19396