

1 120255

5-5 15-165-20128-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 Drill completion date 3/10/68

SE SE SE, SEC. 28, T 17 S, R 16 W/E
330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456

Lease Name Ochs "B" Well # 2

Operator: AFG Energy, Inc.
Name & Address P.O. Box 605
Russell, KS 67665

County Rush 115.70

Well Total Depth 3560 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 379

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor AFG Energy, Inc. License Number 3456

Address P.O. Box 605, Russell, KS 67665

Company to plug at: Hour: 11:30 a.m. Day: 5 Month: 5 Year: 19 89

Plugging proposal received from Terry Piesker

(company name) AFG Energy, Inc. (phone) 913-483-2627

were: 4 1/2" at 3551' PBDT 3502' Perfs at 3325-46 (2 sets) DV tool set at 1125' cemented with 550 sx

1st plug pump 1 sx hulls, 40 sx cement, 14 sx gel, 100 sx cement,

2nd plug pump in 8 5/8" X 4 1/2" annulus as needed.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p.m. Day: 5 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped in 4 1/2" casing with 100 lbs. hulls, 40 sx cement, 14 sx gel, and 100 sx cement. Pumping pressure 0-1000 psi and shut in 900 psi.

Pumped 1/2 barrel water in 8 5/8" X 4 1/2" annulus, 500#.

STATE CORPORATION COMMISSION

MAY 9 1989

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 5-10-89

Signed Dean Parker (TECHNICIAN)

INV. NO. 24737