

1 030492

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,893-0000

C SE SE , SEC. 4 , T 20 S, R 23 W/EK

660 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Kanaga Well # 1-4

Operator: Gear Petroleum Co., Inc.

County Ness 14.5.60

Name & Address 300 Sutton Place

Well Total Depth 4480 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 512

Abandoned Oil Well Gas Well Input Well SMD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 7:00 am Day: 19 Month: August Year: 19 85

Plugging proposal received from Bruce Fickel

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1555' Elevation 2274' KB

1st plug at 1555' with 50 sx cement

2nd plug at 540' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:-0 am Day: 19 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1555' with 50 sx cement, 2nd plug at 540' with 40
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement, 5th plug to circulate rat hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

8-20-85

AUG 20 1985

Signed Steve Durrant (TECHNICIAN)

9688 - 8-19