

1 071122

11-4

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,929-A 00-01

SW NE SE, SEC. 4, T 20 S, R 23 W/E

1650 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4677

Lease Name McCune Well # A-1 OWWO

Operator: Cara Ventures, Inc.

County Ness 145.60

Name: P.O. Box 287

Well Total Depth 4480 feet

Address Attica, KS 67009-0287

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 538

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Cara Ventures, Inc. License Number 4677

Address P.O. Box 287, Attica, KS 67009-0287

Company to plug at: Hour: 6:30 p.m. Day: 4 Month: 11 Year: 19 92

Plugging proposal received from Paul Caragianis

(company name) Cara Ventures (phone) 316-254-7579

were: 4 1/2" at 4346' w/125 sx cement, PBTD 4350', Perfs at 4287-91'

1st plug sand back to 3160' and dump 4 sx cement on top of sand through bailer,

2nd plug shoot pipe at 800', run tubing to 800' and pump 10 sx gel, 2 sx hulls and 75 sx cement,

3rd plug pump 50' sx cement at 570'

4th plug pump 25 sx cement at 300', 5th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 8 p.m. Day: 4 Month: 11 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3160' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped through tubing at 830' with 75 sx cement,

3rd plug at 570' with 40 sx cement,

4th plug at 300' with 25 sx cement,

5th plug topped off with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 837' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~XXXXXX~~) observe this plugging.

Signed Dan Sobwa
(TECHNICIAN)

NOV 17 1992

INVOICED

DATE 12-8-92

NOV NO. 37010

11-4-92 JAN 22 1993