

1 070195

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,208-0000
150' E of
C NW NW, SEC. 12, T 20 S, R 23 (W) #
4620 feet from S section line
4470 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033
Operator: Murfin Drilling Company
Name & Address: 250 N. Water, Suite 300
Wichita, KS 67202

Lease Name Simmitt Well # 1
County Ness 144.30
Well Total Depth 4440 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 467

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033
Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 5:45 pm Day: 18 Month: June Year: 19 86

Plugging proposal received from Ed Lofland
(company name) Murfin (phone) 316-267-3241

were: 5 1/2" at 4439' PBSD 4399, Perfs at 4358-62'; 4365-69'; 4374-78'; 4394-99'
1st plug pump 1 sack hulls and 25 sx cement to bottom

2nd plug Displace w/5 1/2" wiper plug to 4200' w/gelled water. Perforate 2 spf at 900'.

Pump 175 sx cement (don't displace f/csg). If cement does not circulate pump 100 sx cement down annulus.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 8:15 pm Day: 18 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pump 1 sack hulls and 25 sx cement to bottom. 2nd plug displace with 5 1/2" wiper plug to 4200' with gelled water. Perforate 2 spf at 900'.

Pump 175 sx cement - maximum pressure 700 psi and shut in 300 psi. Pumped 100 sx cement down annulus - Maximum pressure 700 psi and shut in 400 psi.

RECEIVED STATE CORPORATION COMMISSION

JUN 23 1986

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE JUN 23 1986
INV. NO. 14177
6-18

Signed Dan Gorka (TECHNICIAN)