

1031308 1-10

API NUMBER 15- 135-23,855-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE NE, SEC. 23, T 20 S, R 23 W/E

TECHNICIAN'S PLUGGING REPORT

2310 feet from NXX section line

330 feet from E section line

Operator License # 31389

Lease Name Reinert Farms, Well # 1
Inc.

Operator: Nobel Petroleum, Inc.

County Ness

Name & Address 3101 N. Rock Rd., Ste. 125

Well Total Depth 4395 142.84 feet

Wichita, KS 67226

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 327

Abandoned Oil Well Gas Well Input Well SMD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 10 Month: 1 Year: 19 95

Plugging proposal received from Rich Wheeler

(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1433-69'

1st plug at 1470' with 50 sx cement, 2nd plug at 750' with 80 sx cement,

3rd plug at 360' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:30 a.m. Day: 10 Month: 1 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 1470' with 50 sx cement,

2nd plug at 750' with 80 sx cement,

3rd plug at 360' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement

RECEIVED STATE CORPORATION COMMISSION

JAN 18 1995

CONSERVATION DIVISION WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (copy did not) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 1-25-95

WELL NO. 42098

1-10 MAR 18 1995

EFFECTIVE DATE: 1-1-95

State of Kansas

FORM MUST BE TYPED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

135-23,855-0000

FORM MUST BE SIGNED

SHAFT TYPE No

Must be approved by the K.C.C. five (5) days prior to commencing well

ALL BLANKS MUST BE FILLED

Expected Spud Date 12 30 94 month day year

Spot SE SE NE Sec 23 Twp 20 S. Rg 23W East West

OPERATOR: License # 31389 Name: NOBEL PETROLEUM, INC Address: 3101 N. Rock Road - Suite 125 City/State/Zip: Wichita, Kansas 67226 Contact Person: Jay. Ablah Phone: 316/636-2222

2310 feet from line of Section 330 feet from East line of Section IS SECTION Y REGULAR IRREGULAR? (NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License # 5929 Name: DUKE DRILLING CO., INC.

County: Ness Lease Name: Reinert Farms, Inc. Field Name:

Well Drilled For: Well Class: Type Equipment: X Oil ... Enh Rec ... X Infield ... X Mud Rotary ... Gas ... Storage ... Pool Ext. ... Air Rotary ... GWD ... Disposal ... Wildcat ... Cable ... Seismic; ... # of Holes ... Other

Is this a Propped/Spaced Field? yes X no Depth to bottom of fresh water: 290 290'

If GWD: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Nearest lease or unit boundary: 330' Ground Surface Elevation: 2223' feet MSL

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location:

Water well within one-quarter mile: X yes no Public water supply well within one mile: yes X no

Exp. 6/27/95

AFFIDAVIT NOTE * MIN 320' FOR ACT II

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Rod Wheeler SPUD DATE JAN 2, 1995 INIT. GB LENGTH SURFACE PLANNED 290

RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 1/2 @ 327 CONDUCTOR ANHYDRITE T-4433 B-4464 ELEVATION

TD 4395 FORMATION 7450 RAN PIPE @ DV TOOL ALT II DONE SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1490 Ft. W/ 50 SX

1/2 Base Anyl. @ 5252 Ft. W/ 50 SX

1/2, 1/2 Plug @ 5252 Ft. W/ SX

Bottom Surface @ 5252 Ft. W/ 40 SX

40' Plug @ 5252 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond Hauling X)

TECHNICIAN SD DATE 1-9-95

TYPE OF CEMENT 6-1/2 1/2 A 125

STARTING TIME 4:00 (AM/PM) DATE 1-10-95

COMPLETION TIME 6:30 (AM/PM) DATE 1-10-95

CEMENT COMPANY Applied