

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135- 22517 - 0000

SE SW NE, Sec. 26, T 20 S, R 23 W/E

330 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Marhofer Well # 1

Operator: Chief Drilling Co., Inc.
Name & 905 Century Plaza
Address Wichita, KS 67202

County Ness

Well Total Depth 4384 feet 142.48

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 306

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Co. # 1 License Number 5674

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 27 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Harold Dinkle

(company name) Warrior Drilling Co. (phone) 913-726-4875

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1440 with 50 sx cement

2nd plug at 750' with 50 sx cement

3rd plug at 360 with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement.

Signed R. Barburton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:30 am Day: 27 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1440 with 50 sx cement, 2nd plug at 750 with

50 sx cement, 3rd plug at 360 with 40 sx cement, 4th & 5th plugs - solid bridge - hulls

plug at 40 -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

15 sx cement.

Remarks: Use 60/40 Pozmix, 2% gel, 3% cc by Halliburton

RECEIVED
STATE CORPORATION COMMISSION

FEB 02 1984

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed R. Barburton
(TECHNICIAN)

2-3-84
0038