

To: 1 1998 2-17
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-135-24,047-0000
NE SE NW, SEC. 27, T 20 S, R 23 W/E
1650 feet from NXX section line
2310 feet from WXE section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5228
Operator: Parrish Corporation
Name & Address 110 S. Main, Ste. 510
Wichita, KS 67202

Lease Name Everhart Well # 1
County Ness 142.94
Well Total Depth 4398 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 692

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor L.D. Drilling License Number 6039
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 2 a.m. Day: 17 Month: 2 Year: 19 98

Plugging proposal received from Norm
(company name) Parrish Corp. (phone) 316-263-8726

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1424-55'
1st plug at 1450' with 50 sx cement,
2nd plug at 720' with 50 sx cement,
3rd plug at 40-0' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:15 a.m. Day: 17 Month: 2 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug at 1450' with 50 sx cement,
2nd plug at 720' with 50 sx cement,
3rd plug at 40-0' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

2-18-98 FEB 18 1998

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE FEB 23 1998
50113
2-17

Signed Steve Durrant
(TECHNICIAN)

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 1-20-98
DISTRICT # 1
SSA7. X. Yes... No

State of Kansas
NOTICE OF INTENTION TO DRILL

135-24,047-0000

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date January 20, 1998
month day year

Spot NE - SE - NW. Sec 27... Twp 20S S, Rg 23W - East West

OPERATOR: License # 5228
Name: Parrish Corporation
Address: 110 South Main, #510
City/State/Zip: Wichita, KS 67202
Contact Person: Lloyd Parrish
Phone: 263-8726

1650 feet from South (North) line of Section
2310 feet from East (West) line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Ness

CONTRACTOR: License #: 6039
Name: L.D. Drilling

Lease Name: Everhart Well #: 1
Field Name: un-named

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Cherokee Sandstone

Nearest lease or unit boundary: 330'
Ground Surface Elevation: 221.2 feet MSL

Water well within one-quarter mile: X yes no
Public water supply well within one mile: yes X no

Well Drilled For: Well Class: Type Equipment:
X Oil Enh Rec X Infield Mud Rotary X
Gas Storage Pool Ext. Air Rotary
OWO X Disposal Wildcat Cable
Seismic; # of Holes Other
Other IF DRY, CONVERT TO ARBUCKLE DISPOSAL

Depth to bottom of fresh water: 270 Feet
Depth to bottom of usable water: 640

Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 660 Feet 660 MIN

If OWMO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Length of Conductor pipe required: _____
Projected Total Depth: 4400

Formation at Total Depth: Mississippi
Water Source for Drilling Operations:

well farm pond X other
Pawnee Creek

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Will Cores Be Taken? yes X no
If yes, proposed zone: _____

Exp. 7/15/98

AFFIDAVIT

660' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Norm
SPUD DATE 2-17-98 INIT. R.L

LENGTH SURFACE PLANNED 660'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 7/8 6 9/8 CONDUCTOR
ANHYDRITE T-1424 B-1455 ELEVATION

TD MISS
FORMATION MISS
RAN 4350 @ SX DV TOOL SX ALT II DONE Y N

Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 1450 Ft. W/ SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 220 Ft. W/ SX
3-40' Plug @ 420 Ft. W/ 1/2 SX

RAT HOLE CIRC/W SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond Hauling X)

TECHNICIAN SB DATE 2-15-98
TYPE OF CEMENT 6/4 Port 6%

STARTING TIME 2:00 (AM/PM) DATE 2-17-98

COMPLETION TIME 4:15 (AM/PM) DATE 2-17-98

CEMENT COMPANY Allied