

1 050452

15-135-22291-0000

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-not available

C NE NW ^S ~~NW~~, SEC. 30, T 20 S, R 23 W/E

4950 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6832

Lease Name Stum Well # 1-30

Operator: Statex Petroleum, Inc.
Name &

County Ness 141.93

Address 300 E. Carpenter Freeway, Suite 1100
Irving, TX 75062

Well Total Depth 4367 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 496 /

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains, Inc. License Number 4072

Address Box 346, Ness City, KS 67560

Company to plug at: Hour: 1:00 pm Day: 11 Month: February Year: 19 85

Plugging proposal received from Clint Base

(company name) Plains, Inc. (phone) 913-793-2592

were: 4 1/2" set at 4367, Perfs at 4349-59'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, and 150 sx cement.

FEB 15 1985

CONSERVATION DIVISION

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:35 pm Day: 11 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls and 150 sx cement.

Maximum pressure 300 psi and shut in 100 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of this form.)

~~I did not~~ observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 2-25-85
INV. NO. 7098
2-11

MAR 15 1985